

# Discussion Outline



- Site Background
- Pre-Design Investigation
- Permitting
- Design Parameters
- Implementation
- Monitoring
- Conclusions



# Site Background



- Bulk petroleum fuel terminal within Portland Harbor
- Has been in continuous operation for more than 100 years
- A recent infrastructure project increased capacity by 20% to approximately 63 million gallons
- Deeper ship berths (40 feet below Columbia River Datum (CRD)) were required to accommodate larger Double Eagle Class Ships
- Previous elevations of ship berths for were 38 feet below CRD



## Pre-Design Investigation





- Northwest Regional Sediment Evaluation Framework (SEF) developed by the United States Army Corps of Engineers (USACE) guided sampling efforts
- Characterize sediment within dredge prism (chemical and physical properties)
- Evaluate disposal options by comparing sediment chemistry to regulatory guidance
- Characterize post-dredging new surface material
- Evaluate stability of the dredge prism sidewall
- Characterize side-wall sediment chemistry that may slough into dredge prism




#### Pre-Design Sampling

- The proposed maintenance dredging area was subdivided into three Dredge Material Management Units (DMMU)
  - DMMU-1 (North berth)
  - DMMU-2 (South berth)
  - DMMU-3 (slopes surrounding DMMU-1 and DMMU-2)
- Sediment vibracore samples were collected to characterize dredge material for disposal, new surface material after dredging, and sediment with the potential to slough into the dredge prism
- Vane shear testing and standard penetration testing (SPT) were performed at one upland location (GP-1) and two in-water locations (GP-2 and GP-3) to assess riverbank stability and sediment sloughing potential around the parameter of the DMMUs




#### Characterization Sampling





#### Geotechnical Sampling





#### Pre-Design Investigation Results

- Sediment analytical samples were evaluated against the SEF criteria and Oregon Department of Environmental Quality (DEQ) Northwest Region (NWR) Clean Fill screening levels.
  - Data screening confirmed that dredge material was suitable for upland landfill disposal
  - New surface material did not exceed SEF screening levels
- Evaluation of geotechnical sampling results:
  - The bank west of the dock was stable for pre- and post-dredge conditions
  - Dredge cuts no steeper than a horizontal to vertical ratio of 2:1 would be relatively stable



#### Permitting



US Army Corps of Engineers









- Permitting requirements included input from these state and federal agencies:
  - USACE (Department of the Army Joint Permit)
  - Oregon Department of State Lands (DSL; Department of the Army Joint Permit)
  - National Oceanic and Atmospheric Administration (NOAA) National Marine Fisheries Service (NMFS; Biological Opinion)
  - US Fish and Wildlife (USFWS)
  - Oregon Department of Fish and Wildlife (ODFW)
  - DEQ (Section 401 Water Quality Certification)
  - City of Portland Bureau of Development Services (BDS; Land Use Compatibility Statement)



# Design Parameters



- Estimates of dredge volumes and production rates
- Dredge type specifications
- Analysis of riverbank soil stability and dredge prism side slopes
- Decant water mass balance and water management
- Sediment disposal
- Construction monitoring requirements




#### **Details of Design**

- Dredging design was based on the use of a 16 CY barge mounted environmental bucket
  - Production rates were estimated to be approximately 125 CY/hr
- Dredge horizontal to vertical slope of 2:1 along shoreline and no dredging in the toe of slope along the shoreline
- Overdredge allowance of 1 foot
- Dredge material dewatered in bin barge and barged to transload facility, solidified and trucked to landfill
- Decant water discharged to City of Portland sanitary sewer pending analysis
- In-situ volume of dredge material = 26,700 CY
- Decant water volume = 1,000,000 gal
- Stabilized dredge material weight = 37,600 tons



#### **Implementation**



- Hickey Marine Enterprises (HME) performed maintenance dredging activities between September 8 and October 13, 2011
- Dredging activities occurred during active terminal conditions
- Dredge material was transported by barge to a transload facility in The Dalles, OR and then trucked to Wasco County landfill for disposal
- Target depth of 40 feet below CRD was achieved



## **Summary of Dredging Activities**

Dredge Material Management Unit	Relative Location	Dredging Dates	Minimum Dredge Elevation	Volume Dredged
DMMU-1 (88,450 sf)	Downstream Slip	9/8, 9/13-9/16, 9/19, 9/28-9/30, 10/13	-40 ft CRD	13,559 CY
DMMU-2 (77,221 sf)	Upstream Slip	9/20, 9/22-9/23, 9/27, 10/3-10/5, 10/10-10/11	-40 ft CRD	12,393 CY












#### Environmental Monitoring Plan



- An Environmental Monitoring Plan was developed based on cumulative permit requirements
- Environmental monitoring included visual observations and water quality measurements
- Visual observations were made from the dock and the shoreline
- Background (upstream) and downstream water quality measurements were collected every 2 hours
- Measurements included turbidity, dissolved oxygen and pH



## Environmental Monitoring Plan





### **Environmental Monitoring Plan**

- Best management practices implemented:
  - Strict bucket control by an experienced equipment operator to minimize disturbance (i.e. not over or under filling bucket, reducing dredge cycle time)
  - Maintenance of floating sorbent boom and deployment of boom in the event of floating debris or sheen
  - Use of global positioning system software to control dredge cuts
  - Sequencing work activities to minimize the extent and duration of in-water disturbances



#### Conclusions



- Pre-design sampling results provided safe design parameters and allowed for disposal of dredge material in an upland landfill
- Dredging operations were completed safely and successfully
- Total dredge volume of 25,952 CY
- Requirements set forth in the Environmental Monitoring Plan and applicable permits were met throughout dredging activities



# Imagine the result THANK YOU

Email: Wesley.Thomas@arcadis-us.com



#### Acknowledgements

- ARCADIS
  - Brooke Bonkoski, P.E.
  - Grant Sprick, P.E.
  - Everyone involved with project work
- Hickey Marine Enterprises

