NAVIGATION STUDIES AND NEW WORK



2016 WEDA Gulf Coast Chapter
Annual Conference
Byron Williams
Deputy Chief, Project
Management
16 November 2016



"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."






PRESENTATION AGENDA

- Pathways for Implementing New Dredging Projects
- Modifications planned along Texas coast






HOW TEXAS FITS IN THE NATIONAL SYSTEM







TEXAS COASTAL NAVIGATION SYSTEM








WHY IMPROVE PROJECTS?

NOT TO SCALE PPX-1 PPX-2 **PANAMAX**






TEU* Capacity~ 2500 **Sub-Panamax** LOA: 675 BEAM: 98 DRAFT: 37.6 DWT: 34,000 TEU* Capacity~ 3500 - 4800 Panamax LOA: 794-845 BEAM: 106 DRAFT: 40.3-44.3 DWT: 24,000 - 65,000 TEU* Capacity~ 6500 Post-Panamax Gen 1 (PPX-1) LOA: 960 BEAM: 131 DRAFT: 46.1 DWT: 80,600 TEU* Capacity: ~8700 Post-Panamax Gen 2 (PPX-2) LOA: 1106 BEAM: 146 DRAFT: 47.6 DWT: 106,800 * Intermodal Shipping Container Measured as a Twenty-foot Equivalent Unit (TEU) Liquid Capacity: 52,100 – 79,200 kg/m³ 45-80 k PEAK DWT Panamax Tankers: LOA: 600-750 Beam 106 Draft: 41.1-46.2 SP. ENGINE 110,000 k Liquid Capacity: 120,315 kg/m³ ROOM DWT PEAK 55

> **Aframax Tankers:** LOA: 806 Beam 140 Draft: 49.1





MODIFY NAVIGATION PROJECTS -BY AUTHORIZATION



*Feasibility Phase includes **alternatives analysis and NEPA compliance** to determine best plan to provide an environmentally sustainable solution which provides economic value to the nation





ADDITIONAL PATHWAYS

- Continuing Authority Program
- Planning Assistance to States
- Estuary Restoration Program
- Other...

(Available for further discussion after this presentation...)





SABINE-NECHES WATERWAY (NAV)

•Status:

- Chiefs Report Complete: 2011
- •Econ Update Complete: OCT 2016
- Potential Construction Start: FY19

Features

- Est. New Work: 98 MCY
- •Deepening SNWW to Beaumont to 48 feet (50 feet in offshore channels)
- •Extending the Entrance Channel 13.2 miles
- Deepening and widening Taylor Bayou
- Adding/enlarging 3 turning basins and/or anchorages
 Bend easing on Sabine-Neches
- Canal and Neches River Channel
- •Bridge reinforcements
- •Dredged Material Management Plan
- Beneficial Use Plan
- •Compensatory Mitigation Plan



PM: Byron Williams





HOUSTON SHIP CHANNEL (NAV)

•Status:


- •FSCA Signed NOV 2015
- •Feasibility Report Complete MAY 2019
- •Chief's Report OCT 2019

•Features:

- Deepening (upstream of Boggy Bayou)
- Selective Widening (Two-Way Vessel Meeting)
- Bend Easings
- •Flare Modifications
- Turning Basins
- Moorings & Anchorage Areas
- Jetty Structures (shoaling)

Bay Bolivar Roads to Boggy Bayou Bayport Ship Channel Barbours Cut Channel Bayou Boggy Bayou to Sims Bayou Sims Bayou to I-610 Bridge I-610 Bridge to Main Turning Basin





| Depth (feet) | |
|--------------|---------|
| MLT | MLLW |
| 45 | 46/46.5 |
| 40* | 41.5 |
| 36 | 37.5 |







GALVESTON HARBOR CHANNEL EXTENSION (NAV)

Status:

- FCSA signed: Jan 2016
- Study Complete: FY17
- Potential Construction
 Start: FY19

Features

 Extending the Galveston Harbor Channel 2,571 ft and deepening from 41 to 46 ft MLLW



PM: Andrea Catanzaro





FREEPORT HARBOR (NAV)

Status:

- Chiefs Report Complete: 2013
- GRR Complete: April 2018
- Potential Construction Start: FY18-21

Features

- Est. New Work: 16.2 MCY
- Deepen Freeport Harbor Channel to 56 feet (58 feet in offshore channel)
- Extend the Outer Bar Channel 7,000 feet
- Enlarge Brazosport Turning Basin to 1,200 feet
- Deepen Brazosport Turning Basin through the Upper Turning Basin to 51 ft
- Deepen and widen the Lower Stauffer Channel to 300 feet wide by 51 feet deep
- Deepen Upper Stauffer Channel to 26 feet



PM: Nick Laskowski





CORPUS CHRISTI SHIP CHANNEL (NAV)

Status:


Chiefs Report Complete: 2003

• LRR Complete: Dec 2015

Potential Construction Start: FY17-FY18

Features

- Est. New Work: 32 MCY
- Four Separable Elements: Navigation (3) and Ecosystem Restoration (1)
- Deepen CCSC from 45 feet to 52 feet and widen segment of main channel to 530 feet
- Construct Barge Shelves adjacent to CCSC
- Construct two ecosystem restoration features (construction complete)
- Deepen extension of La Quinta Channel to 39 feet (construction complete)



PM: Nick Laskowski






BRAZOS ISLAND HARBOR (NAV)

Status:

- Chiefs Report Complete:
 2014
- Ongoing 408/204 report to allow NFS to construct themselves (JAN 2017)
- Potential Construction Start: TBD

Features

- Est. New Work: 14 MCY
- Deepening main channel to 52 ft and entrance channel to 54 ft



PM: Nick Laskowski





(NEW)MATAGORDA SHIP CHANNEL (NAV)

- Status:
 - Study Kickoff: August 2016
 - Chiefs Report Complete:
 July 2019
- Features
 - May Include
 - Deepening/Widening of Existing Channel
 - Substantial Dredging, depending on plan



PM: Sheri Willey






(NEW)JEFFERSON COUNTY STUDY (ER)

Status:

- Kick-off Meeting 3 NOV, 2016
- Chiefs Report Complete: FY 19

Features

- Coastal shoreline restoration
- Use of sediment material from dedicated dredging to construct a marsh
- Beneficial use of dredged material



PM: Alicia Rea, Dennis Thomas





COASTAL TEXAS (CSRM/ER)

- Status:
 - TSP: May 2018
 - Chiefs Report Complete: April 2021
- Features
 - May include
 - Coastal Barrier(s)
 - Major navigation structures
 - Large scale beach nourishment
 - Large ecosystem restoration projects









PM: Sheri Willey, Eddie Irigoyen





VIRTUAL DISTRICT



ON FACEBOOK

www.facebook.com/GalvestonDistrict



ON TWITTER

www.twitter.com/USACEgalveston



ON YOUTUBE

www.YouTube.com/GalvestonDistrict



duids ON DVIDS

www.dvidshub.net/units/USACE-GD



ONLINE

www.swg.usace.army.mil



